RECORD DRAWING TOP 10 ISSUES

1. AutoCAD files must be delivered and located in the correct spatial coordinate system (NAD 83 FL EAST 901).
2. Deliver one digital copy of the coordinate asset table in the form of an Excel spreadsheet.
3. The Excel asset tables must match the asset table listed on the Record Drawing.
4. Identify existing TWA utilities and annotate with size and type. Create connection details to display asset tie-in for water, sewer and reclaim.
5. Transfer approved plan symbols to Record Drawing.
6. Provide XY Coordinates for water meters; reclaim meters and sewer clean-outs.
7. Provide asset ID's with XY Coordinates for all utility assets included in the Record Drawing and asset table.
8. Identify utility pipes and include pipe attributes of size, material and class.
9. Record Drawing project deliverables must include a hard copy of the Record Drawing, a digital copy of the Record Drawing, PDF's and an Excel spreadsheet of the coordinate asset table for every resubmittal.
10. The demarcation of Toho Water Authority maintenance responsibility shall be clearly marked.