**Toho Water Authority Private Development YES** The following items are required. **Project Flow Chart** Toho must witness all pigs being Is your project ready Inspection/Test installed and removed from each for Infrastructure Steps line being performed. Inspection/Testing? Toho Ensure you receive a copy of your Water No projects inspection/testing prior to Authority See open inspector leaving job site. items on your Development **Dashboard Gravity Sanitary Sewer Reuse Water Inspections** The following inspections are The following inspections are require to **Potable Water Inspections** be completed with a Toho inspector. The following inspections are require to be require to be completed with a completed with a Toho inspector. Toho inspector. Gravity sanitary sewer low air test. • Gravity sanitary sewer CCTV. Potable water main pigging. Reuse water main pigging. • Gravity sanitary sewer mandrel test. Potable water main hydrostatic pressure test. Reuse water main Test must be conducted by hand. • Potable water main dis-infection. hydrostatic pressure test. Pulls or video of pull for future Potable water main bacteriological sampling. review without the presence of an FDEP clearance is not required inspector are prohibited. for Reuse **Pre-Final Site Inspection with Submit for FDEP Water clearance Submit for FDEP Wastewater clearance Toho Inspector** (if required) (if required) Consequences of non-compliance. Customer Final Site Inspection with DPM and Inspector. Any work performed or completed Responsibility Underground contractor to schedule with DPM once all in absence of a Toho Inspector may incur fines, project delays, and or prior required inspections have passed. stop work notices until impacts on For Sewer connection or Utility Build Finals (click Toho Toho Water Authority are assessed here) Responsibility