Toho Water Authority Private Development Project Flow Chart

Toho Lift Station Steps

Does your project have a Toho Lift Station?

YES

No
Return to Pre-con and Inspection workflow

Private Lift Station

Public Lift Station

Private Lift Station license required.

- Private Lift Station shall have a flow meter.
- Private Lift Station shall have a 6'x6' easement around meter.
- Toho Water Authority shall have access to meter.
- **See Private Lift Station Policy.**

Complete **Legal Lift Station Conveyance Package-** Package to be provided by DPM.

And

Pay Telemetry Fee
Developers Contractor installs once station is ready.

Pay Telemetry Fee
Developers Contractor installs once station is ready.

Continue to track your progress on Toho Water Development Portal .

Lift Station Construction begins.
Coordinate Inspections with your assigned Inspector.

- Rough-In Inspection completed with Toho Lift Station Electrician.
- Sanitary Sewer Force Main Pigging.
- Sanitary Sewer Force Main Hydrostatic Pressure Test.
- Wet Well Spark Test.
- Odor control where applicable.
- Pre-Start up inspection.
- Start -up Inspection.

Legal Acceptance?
Acceptance and recording of documentation is required prior to Toho signing of FDEP sewer clearance application.

Customer Responsibility

Toho Responsibility