


PLAN



NOTES:

1. ALL RESIDENTIAL AND COMMERCIAL LATERALS SHALL BE 6".
2. THE SINGLE 6" RISER DENOTES THE END OF TOHO'S MAINTENANCE RESPONSIBILITY
3. THE SINGLE 6" TOHO CLEANOUT SHALL BE PLACED ON THE LOT LINE AND WITHIN 24" OF THE RIGHT-OF-WAY LINE
4. NO CLEANOUTS SHALL BE PLACED WITHIN A RIGHT-OF-WAY OR IN A SIDEWALK
5. LATERALS SHALL NOT EXCEED 100' FROM THE MAIN TO TOHO'S CLEANOUT
6. CONNECTIONS TO THE TOHO CLEANOUT'S VERTICAL STANDPIPE ARE NOT PERMITTED
7. FITTINGS USED SHALL NOT EXCEED 45 DEGREES. A MINIMUM OF 12" OF PIPE IS REQUIRED BETWEEN ALL FITTINGS
8. THE SERVICE WYE ON THE 6" VERTICAL STANDPIPE SHALL BE BETWEEN 18" AND 48" FROM FINISHED GRADE
9. NO PLANTINGS, STRUCTURES, OR OTHER UTILITIES, INCLUDING BUT NOT LIMITED TO TELECOM PEDESTALS, ELECTRICAL TRANSFORMERS OR POLES, OR OTHER CLEANOUTS USED FOR TESTING PURPOSES SHALL BE INSTALLED WITHIN 36" OF ANY SIDE OF THE TOHO CLEANOUT.
10. PLACE TOHO APPROVED 3M MARKER TAPE FROM THE MAIN TO THE SINGLE OR DOUBLE SERVICE WYE.
  - 10.1. TAPE SHALL BE BURIED NO DEEPER THAN 6'
  - 10.2. IF MARKER TAPE IS INSTALLED MORE THAN 18" ABOVE A LATERAL DUE TO DEPTH OF THE PIPE, ADDITIONAL TOHO APPROVED WARNING TAPE SHALL BE REQUIRED 12" - 18" ABOVE THE PIPE
11. PROVIDE TOHO APPROVED LOCATE BALLS AT ALL SINGLE AND DOUBLE SERVICE WYES
12. SEE SANITARY CLEANOUT DETAIL TOHO-06 FOR ADDITIONAL NOTES AND REQUIREMENTS